Roof/Drain De-Icing System

Note: Roof/Drain Jigs do not include the heating cable.
Consult the installation inspections for sizing the cable length to the jig.

With the introduction of membrane & rubber roofing materials, the attachment of de-icing cables to the roof has presented a dilemma for roofing specialists. A major concern of property owners is the damage caused by ice damming. The roof drain de-icing jig was created with several things in mind. The jig is lightwieght, inexpensive and uses SRG series de-icing cable without anchoring through the roof membrane. It is easy to customize to job conditions in the field. It adapts easily for use in canales and scuppers on southwestern and flat roof style architecture, both commercial and residential. It is easy to install with small hand tools.

4RDDJ22

6RDDJ22

365R14 RAY

MODEL	UPC	DESCRIPTION
4RDDJ22	40509	Canale/Scupper Jig, consists of 1 frame and 4 rays
6RDDJ22	40510	Flat Roof Drain Jig, consists of 1 frame and 6rays
3625R14 RAY	40511	Cable Keeper / RDDJ-Grid

Call for availability on additional ETI controls not shown above.